

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-20238-00-00
API NUMBER 15-5-16-68
LEASE NAME Giebler
WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely and
return to Cons. Div. office
within 30 days.

SESWSE
330 Ft. from S. Section Line
1650 Ft. from E. Section Line
SEC. 27 TWP. 13 RGE. 20 (E) or (W)
COUNTY Ellis
Date Well Complete 5-16-68
Plugging Commenced 3-23-93
Plugging Completed 3-23-93

LEASE OPERATOR Hallwood Petroleum, Inc.
ADDRESS 4582 South Ulster Street Parkway, Suite 1700, Denver, CO 80237
PHONE # (303) 850-6237 OPERATOR LICENSE NO. 3613
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on _____ (date)
by Dennis Hammell (KCC District Agent's Name).
Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation Arbuckle Depth to Top 3806 Bottom 3816 T.D. 3850
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil/Water	3806	3816	8 5/8	213	None
				4 1/2	3854	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging were used, state the character of same and depth placed, from _____ feet to _____ each set M.I.R.U. - R.I.H. with tubing to 3791'. Spot 20 sx. cement with 100# hulls on bottom, followed with 8 sx. gel. spour to 1610'. Pull tubing to 1610' - spot 75 sx. cement w/200# hulls to circulate at surface. P.O.O.H. with tubing. Squeeze 65 additional sx. cement. Max 500#. S.I. 300#. Hooked-up to 8 5/8" S.P. Pumped in 50 sx. cement with 100# hulls. Max. 700# P.S.I. S.I. 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Cementing License No. 5988
Address 1102 E. Eight, P.O. Box 428, Hays, KS 67601
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HALLWOOD PETROLEUM, INC.

STATE OF COLORADO, COUNTY OF DENVER, ss.

Bruce Hoffman, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bruce Hoffman
(Address) SAME AS OPERATOR

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1993.

M. M. Christian
Notary Public

My Commission Expires: 9/1/93

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1993

CONSERVATION DIVISION
Form CP-4a, Kansas

