

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ellis County, Sec. 27 Twp. 13S Rge. 20W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Giebler "B" Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed July 12 19 52

Application for plugging filed April 15 19 59

Application for plugging approved April 17 19 59

Plugging commenced April 20 19 59

Plugging completed April 20 19 59

Reason for abandonment of well or producing formation Production of Commercial quantities of oil depleted.

If a producing well is abandoned, date of last production April 19 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty - Hays, Kansas

Producing formation Arbuckle Depth to top 3814' Bottom 3830' Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	220'	220'
				5-1/2"	3817'	3817'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement; Set No. 2 Plug at 220' with 20 sacks cement; Set No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P.
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

Subscribed and sworn to before me this 26th day of May, 19 59
My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.



PLUGGING
FILE SEC 27 T 13 R 20W
BOOK PAGE 31 LINE 14

DRILLER'S LOG

Imperial Drilling Company, Inc.
903 Union National Bank Bldg.
Wichita, 2, Kansas

15-051-00055-00-00

Giebler #1
SE SE SW 27-13-20
Ellis County, Kansas

Total Depth: 3830'

Commenced: 6-20-52 Completed: 7-12-52 Production: 304 BOPD
Elevation 2225 K.B.

Contractor: Imperial Drilling Company, Inc.
Wichita, 2, Kansas

Casing Record: Set 220' of 8 5/8" surface pipe w/120 sacks cement.
Set 3817' of 5 1/2" oil string of casing w/225 sacks cement.

Figures indicate bottom of formations:

Tops

Surface Clay & Sand	85'		
Shale & shells	500'		
Sand & Shale	905'	Anhydrite	1527' (- 698)
Shale, shells & sand	1500'	Topeka	3203' (-,978)
Lime & shale	3430'	Heebner	3449' (-1224)
Lime	3525'	Toronto	3487' (-1262)
Lime & shale	3679'	Lansing	3513' (-1288)
Lime	3814'	Conglomerate	3812' (-1587)
Arbuckle	3830'	Arbuckle	3814' (-1589)
Total Depth (Rotary)	3830'	T.D.	3830' (-1605)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Wilford L. Pritchard
Wilford L. Pritchard

Subscribed and sworn to before me this 24th day of July, 1952.

Marguerite Tuttle
Notary Public

My commission expires: Jan 4, 1954

RECEIVED
STATE CONSERVATION COMMISSION

MAY 27 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 27T. 13 R. 204
BOOK PAGE 21 LINE 14