

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

15-051-05395-00-00

Ellis County, Sec. 27 Twp. 13 Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines. NW SW SE
Lease Owner Cooperative Refinery Association
Lease Name Giebler "B" Well No. 2
Office Address Drawer "C", Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-12-53 19
Application for plugging filed May 20 19 63
Application for plugging approved May 20 19 63
Plugging commenced June 22 19 63
Plugging completed June 22 19 63
Reason for abandonment of well or producing formation Non-commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production September 29 19 61
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3813 Bottom 3866 Total Depth of Well 3869 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	oil	3838	3843	8-5/8	248	None
				5-1/2	3869	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 30 sacks of mud 880' to 1000' followed by wooden plug to 880'. Cement from 880' to 800' with plug on top at 800'. Shut in three hours at 500# pressure.

Shot casing at 390'. Pumped 17 sacks of mud, followed with plug, then 17 sacks of cement, followed by plug. Cement plug from 4' to 140'.

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Well Cementing, Inc.
Address P.O. Box 628, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Paul M. Goodwin (employee of owner) or (~~owner or operator~~) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Paul M. Goodwin
Drawer "C" Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 25th day of June, 1963

Donald Woods
Notary Public.



COOPERATIVE REFINERY ASSOCIATION
 Drawer "C"
 Great Bend, Kansas

Well Log Cooperative Refinery Association
 Giebler "B" No. 2
 NW SW SE 27-13-20
 Ellis County, Kansas

1505105395.00.00

Elevation 2217' DF
 Date Commenced 9-14-53
 Date Completed 11-12-53
 Initial Production 472 BOPD
 Arbuckle 3838'-3843'

CASING RECORD: 8-5/8" @ 248 w/150
 5-1/2" @ 3869 w/125

<u>LOG</u>		
<u>From</u>	<u>To</u>	<u>Formation</u>
0	16	Surface
16	75	Limestone
75	340	Sandy Shale
340	412	Limestone
412	850	Sandstone & Shale
850	1220	Limestone
1220	1520	Shale
1520	1550	Anhydrite
1550	1895	Shale
1895	2175	Salt, Anhydrite & Shale
2175	3196	Limestone & Shale
3196	3307	Limestone
3307	3810	Limestone & Shale
3810	3869	Dolomite

<u>GEOLOGICAL TOPS</u>	
Heebner	3444'
Toronto	3465'
L-KC	3481'
Conglomerate	3807'
Arbuckle	3813'
RTD	3869'

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 3 1963
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

Stobler No 12

Elevation: 2217 D.P.
 Casing: 240' of 6-5/8" 2W
 w/150 on Formin 2 on 66

90' 1 1/2" 10-0 10690' w/225
 on Formin

Com: 9-17-53 Comp: 10-2-53
 Total Depth: 365' D.P.

Loc: NW 1/4
 Sec: 27-23-23
 Ellis County, Kansas.
 Operator: Cooperative Refinery Assoc.
 Contractor: Cooperative Refinery Assoc.

Log	Fe	Formation	
0	240	Surface Hole	15051053950000
240	1270	Shale Sand & Shells	
1270	1520	Shale & Red Dod	
1520	1560	Anhydrite & Red Dod	
1560	1715	Red Dod, Shale & Shells	
1715	2030	Shale & Shells	
2030	2495	Shale & Linc	
2495	2470	Linc	
2470	2610	Linc & Shale	
2610	2670	Linc	
2670	3345	Linc & Shale	
3345	3390	Linc	
3390	3430	Linc & Shale	
3430	3650	Linc	
3650	3600	Linc & Shale	
3600	3720	Linc	
3720	3800	Linc & Shale	
3800	3869	Coring	

STATE OF KANSAS 33
 DARRON COUNTY

I hereby certify that the above is a true and correct copy of the log
 on the Stobler No 12 well, located in SW 1/4, Section 27-23-23, Ellis
 County, Kansas.

L. M. Collins

Subscribed and sworn to before me this 5 day of Oct, 1953.

Donald [Signature]
 Notary Public

My commission expires: Aug 17, 1957