

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,157 ²¹³⁴¹⁻⁰⁰⁻⁰⁰

LEASE NAME BEFORT B

WELL NUMBER 1

SPOT LOCATION C NE NW

SEC. 27 TWP. 13 RGE. 20 (E) or (W)

COUNTY ELLIS

Date Well Completed 7-9-81

Plugging Commenced 10-23-84

Plugging Completed 10-23-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH HAYS KS 67601

PHONE # (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation LKC Depth to top 3477 bottom 1632 T.D. 3890

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>SURFACE</u>		<u>215</u>	<u>surf</u>	<u>8 5/8"</u>	<u>215'</u>	<u>NONE</u>
<u>PRODUCTION</u>		<u>3880</u>		<u>4 1/2"</u>	<u>3880'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dug out cellar below casing support. Cut off 8 5/8" casing below casing support. Dropped line and tagged cement at 48' Put 15 sacks in anilis free flow. Pumped 40 sx of 50/50 pozmix 6% gel 3% c.c. and 3 sx hulls into 4 1/2" casing. Then pumped 11 sx Cell 1/2 sx hulls and released plug. Pumped 130 sx cement and pressured to 400 psi-shut in pressure approximate 100psi. Finished at 3:30 p.m.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION License No. 719
Address 207 W 12TH HAYS KS 67601

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF ELLIS, ss.

DEC 13 1984

DAN A NIXON (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) [Signature]

(Address) _____

SUBSCRIBED AND SWORN TO
LORNA M. HERRMAN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 6-19-88

before me this 12th day of December, 1984
Lorna M. Herrman
Notary Public

My Commission expires: _____