

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21358-00-00

LEASE NAME Geibler "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 27 TWP. 13 RGE. 20 (X) or (W)

COUNTY Ellis

LEASE OPERATOR BHP Petroleum (Americas) Inc.

ADDRESS 925 Patton Road, Great Bend, KS. 67530

PHONE# (316) 792-2756 OPERATORS LICENSE NO. 4655

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 8-6-77

Plugging Commenced 8-5-86

Plugging Completed 8-5-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS.

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation L-KC Depth to Top 3550 Bottom 3760 T.D. 3865

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	oil	3550	3760	8-5/8	220	0
Arbuckle	oil	3850	3865	5-1/2	3857	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforated 2 holes at 1500-01 & 2 holes 750-51'. Ran tubing. 1st plug 50 sacks of econical lite cement 3810' to 2600'. 2nd plug 90 sx of econical lite cement 2567 to surface. Cement circulated. Squeezed tbg w/15 sx of lite, SI press. 6000 psi. Pressured annulus to 1100 psi but wouldn't take cement. Job complete at 11:45 a.m.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Box 428, Hays, KS. 67601

STATE OF Kansas COUNTY OF Barton, ss.

Bill R. Wriston (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bill R. Wriston

(Address) 925 Patton Rd., Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1986

Ronald E. Rowe
Notary Public

My Commission Expires: My Appt. Exp. Sept. 9, 1987



SEP 16 1986

09-16-86

DRILLERS LOG

No. 1 Giebler 'A'

CASING RECORD:

3 5/8" @ 220'
1/150 sx cement

1 1/2" @ 3,857'
1/150 sx cement

TOTAL DEPTH: 3,865'

COMPANY: B. J. Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: July 12, 1977

COMPLETED: July 20, 1977

DESCRIPTION:

C N/2 S/2 SW/4
Sec. 27-T13S-R20W
Ellis County, Kansas

ELEVATION: 2,252' KB

FORMATION

Surface Clay
Soft Rock & Shale
Shale
Clay, Shale & Sand
Shale
Anhydrite
Shale
Lime & Shale
Lime
TD

FROM

0
40
228
250
1310
1564
1604
1970
3120

TO

40
228
250
1310
1564
1604
3120
3865
3865

REMARKS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 26th day of July, 1977.

Joyce A. Hagermann
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

JUL 24 1986

