

API NUMBER 15-051-23,513 *0000*

LEASE NAME Geibler "A"

WELL NUMBER 2

660 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 13 RGE. 20 (X) or (W)

COUNTY Ellis

Date Well Completed 7-28-83

Plugging Commenced 8-6-86

Plugging Completed 8-6-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR BHP Petroleum (Americas) Inc.

ADDRESS 925 Patton Rd., Great Bend, KS. 67530

PHONE#(316) 792-2756 OPERATORS LICENSE NO. 4655

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is AC0-1 filed? yes If not, is well log attached? yes

Producing Formation L-KC Depth to Top 3495 Bottom 3700 T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size  | Put in | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| Topeka    | oil     | 3245 | 54   | 8-5/8 | 308    | 0          |
| L-KC      | oil     | 3495 | 3700 | 5-1/2 | 3839   | 0          |
| Arbuckle  | oil     | 3833 | 36   |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran tubing. 1st plug 50 sx econical lite cement from 3828' to 2738'. 2nd plug 100 sx econical lite cement from 2565 to surface. Cement circulated. Squeezed top w/ 40 sx of lite cement. SI pressure 750 psi. Pressured annulus to 700 psi, couldn't pump cement. Job complete at 11:15 a.m.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Box 428, Hays, KS. 67601

STATE OF Kansas COUNTY OF Barton, ss.

Bill R. Wriston (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bill R. Wriston

(Address) 925 Patton Rd., Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1986

Ronald E. Rowe  
 Notary Public

My Commission Expires: My Appt. Exp. Sept. 9, 1987



09-16-86  
 SEP 7 6 1986

GIEBLER A-2  
SW/4 Sec. 27-13S-20W  
Ellis County, Kansas

Commenced: 7-12-83

Completed: 7-18-83

Operator: Monsanto Oil Company

15051-23513-00-00

| Depth    |      | Formation          | Remarks  |  |
|----------|------|--------------------|--|--|
| From     | To   |                    |  |  |
| 0        | 315  | Surface Clay-Shale | Ran 7 jts. of 24# 8 5/8" csg. set @ 308' cemented w/175 sks. Posmix 60/40 3% CC-2% Gel PD @ 3:00PM 7-12-83 |  |
| 315      | 1535 | Shale              |  |  |
| 1535     | 1580 | Anhy               |  |  |
| 1580     | 1663 | Shale              |  |  |
| 1663     | 2213 | Shale-Redbed-Lime  |  |  |
| 2213     | 2615 | Shale-Lime         |  |  |
| 2615     | 2966 | Lime-Shale         |  |  |
| 2966     | 3363 | Shale-Lime         |  |  |
| 3363     | 3724 | Lime-Shale         |  | Ran 95 jts. of 15 1/2# 5 1/2" csg. set @ 3839' cemented w/75 sks. 50/50 Posmix-2% Gel- 10% salt- 100 sks. common 18% salt- 5% Calseal PD @ 9:30 AM 7-18-83 |
| 3724     | 3760 | Shale-Lime         |  |  |
| 3760     | 3821 | Lime-Shale         |  |  |
| 3821     | 3840 | Lime               |  |  |
|          |      |                    |  |  |
| 3840- TD |      |                    |  |  |

State of Kansas )

County of Sedgwick )

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton, II*  
James S. Sutton, II-President



Subscribed & Sworn to before me  
this twenty-second day of July, 1983.

*Lola Lenore Costa*

Lola Lenore Costa

My Commission expires November 21, 1984.