

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15051-05134-00-00
 Comp. 8/55
 LEASE NAME Kingsley

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2
¹⁹⁸⁰
~~2310~~ ⁴⁴ Ft. from S Section Line
~~2310~~
~~4950~~ Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC. 34 TWP. 13 RGE. 20W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY Ellis

PHONE# () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 8/55

Character of Well oil

Plugging Commenced 2/28/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/28/95

The plugging proposal was approved on _____ (date)
 by _____ (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? no

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	160	
				5 1/2	3863	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Perf 2300', 1540' & 860', 2 SPF. Ran 2 3/8" tbg 3539'. Spot 150 sx 65/35 Poz w/6% gel & 450 hulls. Pull tbg to 1519', pump 125 sx 65/35 Poz w/6% gel, cmt. circ. to surface. Pulled tbg out, pump dwn 5 1/2" csg w/150 sx 65/35 Poz w/6% gel, MP 500#, SI w/200#. Hook up to 8 5/8" (If additional description is necessary, use BACK of this form.) csg, braden head leaking, repaired. Pump 115 sx 65/35 Poz w/6% gel, MP 100#, SI 100#.

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606
 Address Wichita, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Larry M. Jack

(Address) Wichita, KS



SWORN TO before me this 23 day of March, 19 95

Kerran Redington
 Notary Public
 Kerran Redington

My Commission Expires: 2/6/98