

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15051-20670-00-00  
API NUMBER 15-11-17-70  
LEASE NAME Storm  
WELL NUMBER #2

TYPE OR PRINT  
NOTICE: Fill out completely and  
return to Cons. Div. office  
within 30 days.

S2NWNE  
4290 Ft. from S. Section Line  
1980 Ft. from E. Section Line  
SEC. 34 TWP. 13 RGE. 20 (E) or (W)  
COUNTY Ellis  
Date Well Complete  
Plugging Commenced 3-24-93  
Plugging Completed 3-24-93

LEASE OPERATOR Hallwood Petroleum, Inc.  
ADDRESS 4582 South Ulster Street Parkway, Suite 1700, Denver, CO 80237  
PHONE # (303) 850-6237 OPERATOR LICENSE NO. 3613  
Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on \_\_\_\_\_ (date)  
by \_\_\_\_\_ (KCC District Agent's Name).  
Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3829 Bottom 3836 T.D. 3836  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation  | Content   | From | To   | Size           | Put in      | Pulled out   |
|------------|-----------|------|------|----------------|-------------|--------------|
| Arbuckle   | Oil/Water | 3829 | 3836 |                |             |              |
| LKC AB J K | Oil/Water | 3491 | 3697 | 8 5/8<br>5 1/2 | 206<br>3829 | None<br>None |
|            |           |      |      |                |             |              |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ each set R.I.H. with tubing to 3820', spot 75 sx. cement with 300# hulls with T.O.C. at 3200'. Pulled up 3200', spot 12 sx. gel. Pulled tubing to 1540', spot 100 sx. cement with 100# hulls to circulate to surface. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing, squeezed 25 sx. cement. Max. 500# P.S.I. S.I. 300#. Hooked-up to 8 5/8" surface pipe, squeezed 60 sxs. cement. Max. 400# P.S.I. S.I. 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Cementing License No. 5988  
Address 1102 E. Eight, P.O. Box 428, Hays, KS 67601  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HALLWOOD PETROLEUM, INC.

STATE OF COLORADO, COUNTY OF DENVER, ss.

Bruce Hoffman, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bruce Hoffman  
(Address) SAME AS OPERATOR  
SUBSCRIBED AND SWORN TO before me this 13th day of April 1993  
Notary Public Ada M. Christian

My Commission Expires: 9/1/93

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-4