

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-23504-00-00

LEASE NAME Nicholson

WELL NUMBER 10

330 Ft. from N Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 13S RGE. 20 (E) or (W)

COUNTY Ellis

Date Well Completed 8-23-83

Plugging Commenced 12-7-89

Plugging Completed 12-7-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Quinoco Petroleum, Inc.

ADDRESS P O Box 378111 Denver, CO 80237

PHONE# (303) 850-7373 OPERATORS LICENSE NO. 03613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-7-89 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing Formation Marmaton Depth to Top 3809 Bottom 3832 T.D. 3847

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf	To	Size	Put In	Pulled out
Arbuckle	Oil	Surf	308'	8 5/8"	7 jts	
Marmaton	Oil	Surf	3841'	5 1/2"	96 jts	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pumped 260 sx 60/40 pox w/8% gel mixed w/500# hulls. Pumped 15 sx into 8 5/8" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P O Box 579 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

Suzanne E. Meadows, Sr. Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Suzanne E. Meadows

(Address) P.O. Box 378111 Denver CO 80231

SUBSCRIBED AND SWORN TO before me this 16<sup>th</sup> day of April, 19 90

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Robert Carlisle  
Notary Public

My Commission Expires: May 21, 1990

GABBERT-JONES, INC.

--DRILLERS WELL LOG--

15-051-2350400-00

NICHOLSON #10  
NW-NE-NW Sec. 34-13S-20W  
Ellis County, Kansas

COMMENCED: 6-22-83

COMPLETED: 6-28-83

OPERATOR: MONSANTO OIL CO.

Depth		Formation	Remarks
From	To		
0	310	Surface Clay-Shale	
310	2121	Shale	
2121	3515	Shale-Lime	
3515	3634	Lime-Shale	
3634	3746	Lime	
3746	3838	Lime-Shale	
3838	3843	Lime	
3843 - TD			

Ran 7 jts. of 24# 8 5/8" csg.  
set @ 308'-Cemented w/175 sks.  
60/40 Posmix 3% CC-2% Gel  
PD @ 10:45 P.M. 6-22-83

Ran 96 jts. of 17# 5 1/2" csg.  
set @ 3842'-Cemented w/100 sks.  
Common 5% Calseal 18% Salt -  
75 sks 50/50 Posmix 2% Gel  
PD @ 2:15 A.M. 6-28-83

State of Kansas ]  
County of Sedgwick ]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.


GABBERT-JONES, INC.

James S. Sutton, II - Pres.

Subscribed & sworn to before me  
this 5th day of July, 1983.

Lola Lenore Costa - Notary Public

My Commission expires November 21, 1984.



RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1983  
INSPECTION DIVISION  
Wichita, Kansas