

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-051-30238-00-00

LEASE NAME KINGSLEY

TYPE OR PRINT

WELL NUMBER 3

NOTICE: Fill out **completely** 1650 Ft. from S Section Line  
and return to Cons. Div. 990 Ft. from E Section Line  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC. 34 TWP. 13S RGE. 20W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Ellis  
PHONE # ( ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 8/65  
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 03/27/02  
Plugging Completed 03/27/02

The plugging proposal was approved on 03/27/02 (date)  
by Jay Pfeifer @ KCC in Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 3844 Bottom 3855 TD 3852'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	220'	8 5/8		0
		Production	5 1/2"	3844		0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows: Ran 2 3/8" workstring to 1972' (tag solid) talk w/KCC. Plug at 1972'. Pumped 80 sxs. Cement & 300# hulls at 1950' pulled tbg. to 900' pumped 85 sxs & 300# hulls, cement circ. To surface. TOH w/tbg. Hooked up to 5 1/2 csg pumped 75 sxs cent. 200# washed up. Witnessed by Jay Pfeifer w/KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED

APR 04 2002

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc. KCC WICHITA

STATE OF KANSAS COUNTY OF SEDGWICK .SS.


Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 1 28th day of Mar. 2002

Notary Public - Barbara J. Dodson

My Commission Expires: 12/10/03 Form CP-4 Revised 05-88



OR

# WELL LOG

COMPANY **Murfin Drilling Company, et al**

SEC. 34 T. 13S R. 20W

FARM **KINGSLEY** NO. 3

LOC. **SW NE SE**

RIG. NO. **11**

TOTAL DEPTH **3842 & 3852'**


COMM. **8-11-65** COMP. **8-20-65**

SHOT OR TREATED

CONTRACTOR

ISSUED

COUNTRY **Ellis**  
**KANSAS**



CASING

20 10  
15 5/8" 220' w/165 sacks  
12 6  
13 1/2" 3844' w/175 sacks

ELEVATION **2268 KB**  
*(2264)*

PRODUCTION **oil<sub>2</sub>**

FIGURES INDICATE BOTTOM OF FORMATIONS

128	Surface Clay
148	Sand
220	Shale & Post Rock
450	Blue Shale
805	Grey Shale & Shells
850	Sand
1020	Shale
1250	Sand
1543	Red Bed
1587	Anhydrite
1965	Shale & Shells
2490	Shale & Lime
2825	Lime & Shale
3250	Shale & Lime
3847	Lime
3852	Arbuckle
3852'	RTD

*15-051-30238-00-00*

State of KANSAS  
County of SEDGWICK } ss:

I, C. Robert Buford of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Kingsley #3 well.

MURFIN DRILLING COMPANY

By: C. Robert Buford  
C. Robert Buford

Subscribed and sworn to before me this 7th day of September 19 65

My Commission Expires: ADELA WISNIEWSKI, Notary Public  
My commission expires November 5, 1966

Adela Wisniewski  
NOTARY PUBLIC

**RECEIVED**  
**MAR 15 2002**  
**KCC WICHITA**

**ALLIED CEMENTING CO., INC.**

P.O. BOX 31  
 RUSSELL, KS 67665  
 PH (785) 483-3887  
 FAX (785) 483-5566  
 FEDERAL TAX ID# 48-0727860

I N V O I C E

Invoice Number: 086857

Invoice Date: 03/31/02

Sold Murfin Drilling Co.  
 To: 250 N. Water, St. #300  
 Wichita, KS  
 67202

15 051 30238 00 00

Cust. I.D. ....: Murfin  
 P.O. Number ...: Kingsley #3  
 P.O. Date .....: 03/31/02  
 Due Date ...: 04/30/02  
 Terms .....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	144.00	SKS	6.6500	957.60	T
Pozmix	96.00	SKS	3.5500	340.80	T
Gel	30.00	SKS	10.0000	300.00	T
Hulls	6.00	SKS	18.0000	108.00	T
Handling	276.00	SKS	1.1000	303.60	T
Mileage (18)	18.00	MILE	11.0400	198.72	T
276 sks @\$ .04 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	18.00	MILE	3.0000	54.00	T

All Prices Are Net, Payable 30 Days Following  
 Date of Invoice. 1 1/2% Charged Thereafter.  
 If Account CURRENT take Discount of \$ 273.78  
 ONLY if paid within 30 days from Invoice Date

Subtotal: 2737.72  
 Tax.....: 175.22  
 Payments: 0.00  
 Total....: 2912.94

RECEIVED  
 APR 04 2002  
 KCC WICHITA

