



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 10 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Dallas Sullivan of S & C Drilling, Inc., has this

date requested permission to plug the following described well:

Wycoff Bros. Oil Co.

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Wycoff Brothers Oil Company,

Complete Address: Russell Springs, Kansas.

Lease Name: Molby Well No. 1

Location: CSE-SW Sec. 17 Twp. 13 Rge. (E) (W) 34

County Logan Total Depth 3290 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Sullivan was instructed to plug the well as follows:

103'--8 5/8" Surface pipe, cement circulated.

Circulate hole at top of fish with heavy mud, set plug @ 95'

with 1/4 Sk hulls and displace 20 Sx cement thru DP. Heavy mud

to 40', set plug with 1/2 Sk. hulls and 10 Sx cement to bottom

of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent