



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gene Lay of Rine Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Lay guarantees payment of the plugging fee.

Operator's full Name: Bradley-Shaw

Complete Address: 826 Union Center Building, Wichita, Kansas.

Lease Name: Finley Well No. 1

Location: CNE-SE Sec. 13 Twp. 13 Rge. (E)(W) 40

County: Wallace Total Depth 5270' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lay was instructed to plug the well as follows:

317'--8 5/8" Surface casing, cement circulated with 250 Sx.

Circulate hole with heavy mud. Pull DP to 390' and displace 40 Sx. cement thru DP. Pull DP to 40', set bridge with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. J. J. J.

Conservation Division Agent