

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

July 22, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

RCWD
07-22-81

Dear Sir:

Mr. Marion Burris of Warrior Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Patrick Petroleum Corporation

Complete Address: Suite 400, 120 Bldg., 120 S. Market, Wichita, Kansas 67202

Lease Name: Ward Well No. 1

Location: C SE NW Sec. 20 Twp. 13 Rge. 35 (E) (W)

County: Logan Total Depth: 4590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Burris was instructed to plug the well as follows:

8 5/8" - 408' - 200 sacks Common 2% gel - 3% c.c. Elev. 2981 KB - Anhydrite 2314-36'
Dakota 1740' - 1900' Circulate and Fill hole with mud. Pump 50
sacks cement through drill pipe at 1984'. Pump 50 sacks
Cement through drill pipe at 1700'. Pump 30 sacks
Cement through drill pipe at 400'. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement.
Cement rat hole with 10 sacks.

Very truly yours,

Conservation Division Agent