

15-199-00100-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 107-36

LOCATION SW SE NE

SEC. 24 TWP. 13 RGE. 43 **W**

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ~~Alvard~~ Alvard

Operator Skelly Oil Co Address Box 1650 Tulsa, Okla

Field _____ County Wallace

Total Depth 5241 Feet.

Plugging Contractor Hulme Drg Co & Halliburton Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

13" at 435' circulated with cement - 8 5/8" at 2895' with
400 sax cement behind.

Spotted 50 sax cement through drill pipe on bottom - mud to

4992', spotted 25 sax cement through drill pipe at 4992 - mud to

2895', spotted 25 sax cement through drill pipe 2895' to 2813' -

pulled 447' 8 5/8" - mud to 420', spotted 25 sax cement through

drill pipe 420' to 385' - mud to 38' set plug and 30 sax cement

to bottom cellar. Cementing by Halliburton Cementing Co.

Edwin Petty
District Conservation Agent

Date 10-20-56

PLUGGING
FILE SEC T RIVED
BOOK PAGE LINE DIVISION COMMISSION

10-29-56
DIVISION