

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-109-20024-00-00  
RECEIVED  
STATE CORPORATION COMMISSION  
JUL 30 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,  
Complete Address R. R. #2, Victoria, Kansas.  
Lease Name Darnell Well No. 1  
Location SE-SE-SW Sec. 32 Twp. 13 Rge. (E) (W) 35  
County Logan Total Depth 4850'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 2:00 PM Day 25 Month 7 Year 1973

The above well was plugged as follows:

161'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 110 Cu. Ft. cement  
thru DP from 1350' to 1025'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru  
DP from 185' to 110'. Pulled DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 7-30-73

INV. NO. 7700-W