

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasFEB 7 1964
02-07-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Drillers Producers Pipe & Supply Co., Inc.

Complete Address: Box 368, Great Bend, Kansas

Lease Name Cudney Well No. # 1

Location C NE NE NW Sec. 27 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4476

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:00AM Day 6th Month Feb. Year 1964

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cemented with 250 sacks. 4476' of 5 1/2" long string, cemented with 150 sacks. Bottom of hole was sanded to 4400', and cemented with 5 sacks. Fluid level was up in hole, and would not bail down. Plug was pushed to 300', and 10' rock bridge. 5 sacks cement was mixed in a barrel and put on plug, through the dump bailer, and let set over night. Next morning hole bailed down, and 20 sacks cement was added to plug. Hole was filled with mud to 40', 10' rock bridge, and cemented with 10 sacks to base cellar. 3447' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

Archie Elving
Well Plugging SupervisorDATE 2/7/64INV. NO. 8599-W