

15-199-00014-06-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1972
07-19-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address 1860 Lincoln St. Denver, Colorado

Lease Name N. D. Sexon Well No. 1

Location NW NE SW Sec. 19 Twp. 13 Rge. (E) (W) 32

County Wallace Total Depth 5588'

Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3 P Day 17 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 5588' 13 3/8 csg set at 436' cwc 400 sk.

8 5/8 csg set at 2905' cw 420 sk. Top of cmt. (11420')

5 1/2 csg set at 5188' cw 200 sk cmt. Top of cmt. (5014')

Set 50 sk cmt plug thru tbg. top of cmt(4335')

Cutoff and recovered 3400' of 5 1/2 csg. & 200' of 8 5/8 csg.

Set rock & sand bridge ((190-200')) Dumped 50 sk cmt. (140-190')

Mud to 35' -set rock & sand bridge (25-35) Filled W/25 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 7/19/72

INV. NO. 6048-W