



15-051-22893-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Dave Boyle Rig#2 of Aldrill Exploration has this date requested permission to plug the following described well:

Operator's Full Name: Grant Oil-Remco L.T.D. 1981

Complete Address: 1950 S. Jewell Ave, Suite 106, Lakewood, Co. 80226

Lease Name: Brungardt Well No. 1-30

Location: SE SE SE Sec. 30 Twp. 14 Rge. 16 (E) (W)

County: Ellis Total Depth: 3560'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Boyle was instructed to plug the well as follows:

8 5/8"-180' S.P. cuc w/200 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
03-15-1982  
MAR 15 1982

CONSERVATION DIVISION  
Wichita, Kansas