



15-051-20190-00-00

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

JAN 5 1968  
01-05-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of L. J. Dreiling & Sons has this  
date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Joseph Furthmeyer

Complete Address: Gorham, Kansas

Lease Name: Furthmeyer Well No. 1

Location: SW NE NE Sec. 28 Twp. 14 Rge. 16(E)(W) X

County: Ellis Total Depth 3390' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 500' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

R. J. Massey  
Conservation Division Agent