



15-169-20168-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 31, 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent) RECEIVED
STATE CORPORATION COMMISSION

FEB - 8 1982
02-08-1982
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. D. McDonald of Kansas Drilling & Well Serv. has this date requested permission to plug the following described well:

Operator's Full Name: R. J. Walker Oil Co., Inc. Four Corp Plaza, Suite 150,

Complete Address: 3524 NW 56th St., Oklahoma City, Okla 73112

Lease Name: T. H. Kelly Co., Inc. Well No. 1-19

Location: C NW NW NE Sec. 19 Twp. 14 Rge. 1 (E) (W)

County: Saline Total Depth: 3668'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. McDonald was instructed to plug the well as follows:

Circulate hole and fill with mud. Pump 50 sacks cement
through drill pipe at 300'. Fill hole with mud to 40'
Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Cement rat hole with 10 sacks cement.
Cement mousehole with 5 sacks cement.

Very truly yours,

Conservation Division Agent