

State of Kansas



15-169-20095-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR - 4 1979
04-04-1979
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Harry Hughes of Triangle Drlg. of El Dorado, Inc. has this date requested permission to plug the following described well:

Mr. Hughes guarantees payment of the plugging fee.

Operator's full Name: Rex and Morris Drilling Company

Complete Address: P.O. Box 334, El Dorado, Kansas 67042

Lease Name: Rawline Well No. 1

Location: NW NW NE Sec. 36 Twp. 14 Rge. 1 (W) X

County: Saline Total Depth 2580' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hughes was instructed to plug the well as follows:

8 3/4" - 201-cem. circ. Fill hole with mud to 190'. Push plug and 1/2 sack hulls to 190' and cement hole with 25 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks Cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent