



15-169-20080-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

September 15, 1977

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
CORPORATION

SEP 20 1977
09-20-1977
CONSERVATION
Wichita, K.

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Stubbleford of Transamerica Oil Corporation has this date requested permission to plug the following described well:

Mr. Stubbleford guarantees payment of the plugging fee.

Operator's full Name: Hutchinson's Oil Company

Complete Address: 1223 Douglas Bldg., Wichita, Kansas

Lease Name: Malmstrom Well No. 1 (Doc's Hope)

Location: SE SE SW Sec. 15 Twp. 14 Rge. 2 (E) (W)

County: Saline Total Depth 3381' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Stubbleford was instructed to plug the well as follows:

8 5/8" surface casing set at 162' - cement circulated -
Fill hole with mud - Pump 35 sacks cement through
drill pipe at 175'. Push plug and 1/2 sack hulls to
40' and cap hole with 13 sacks cement. Bridge rathole
and cement with 2 sacks cement

Very truly yours,

Conservation Division Agent