

KANSAS

Form CP-3
Rev. 6-4-68

AL STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT
RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hessing Petroleum Company 15-051-05098-00-00

Complete Address Box 486 Great Bend, Kansas 67530

Lease Name Weber Well No. 2

Location G N/2 N/2 S1 Sec. 27 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3537'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pico Pullers, Inc.

Address Box 486 Great Bend, Kansas License No. 402

Operation Completed: Hour 12:15 P Day 29 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3537' 8 5/8 csg set at 125' c/c 100 skt.

5 1/2 csg set at 3528' c/c 75 skt cmt.

Tubing packer stuck on bottom, rods could not be unseated.

Backed off rods at 1000' - cut off tubing at 520'.

5 1/2 csg squeezed in Dakota Section.

Pressured up on annulus (5 1/2 - 8 5/8) 500 lbs.

Squeezed 5 1/2 csg with 10 skt gel and 150 skt reg poz 11/63 gel.

Test pres. 700 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo M. ...
Well Plugging Supervisor

DATE 10/1/70

INV. NO. 2603-11