

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1960  
CONSERVATION DIVISION  
Wichita, Kansas

20:  
Charles H. Ogden, Director  
900 Insurance Building  
202 North Market  
Wichita 2, Kansas

File No. 15-051-02778-00-00 County: Ellis

Location: SE 1/4 NW 1/4 Sec. 27 Twp. 13 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3634

I have this date completed supervision of plugging of:

Lease Name: Goist Well No. 9

Operator's Full Name: D. R. Lauck

Complete Address: 301 S Broadway Wichita, Kans

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 19 Month 4 Year 60

The above well was plugged as follows:

8 5/8" 140' circulated with cement - 5 1/2" 3634' with 100 sack cement. Plugged back to 3432' 3604', perforated 3562'.

Filled with sand to 3540', set 4 sack cement with dump bailer, pulled 2825'

5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500', displaced

20 sack cement through 5 1/2" at 500', heavy mud to 200', displaced 20 sack

cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10

to bottom collar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

R.A. 4/28/60  
1258 W.