

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company 15251-01702-00-00

Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202

Lease Name Madden Well No. 5

Location SW SW NE Sec. 4 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3595'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address Russell, Kansas 67665 License No.

Operation Completed: Hour 9:50 A Day 1 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3595' 8 5/8 csg set at 206' cwc 135 sk.

5 1/2 csg set at 3576 1/2 cw 150 sk cem.

5 1/2 csg perf. (3357-3408)

2 stage collar set at 1240' & circ to surface with 325 sk cem. No pipe recovered.

Pumped down 5 1/2 csg with 25 sk cement -30 sk gel & water W/400 lbs hulls -released

plug and pumped 50 sk cement. MPP 350 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 5/8/74
9039-W