

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frontier Oil Company 15-051-01692-00-00
Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202
Lease Name Madden Well No. 3
Location NW NW NE Sec. 4 Twp. 13 Rge. (E) (W) 17
County Ellis Total Depth 3605'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by Allied Cementing Co.
Address Russell, Kansas 67665 License No.
Operation Completed: Hour 12:10 P Day 1 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3605' 8 5/8 csg set at 210' cwc 135 sk.
5 1/2 csg set at 3581'ow 150 sk cem.
5 1/2 csg perf. (3349-3508)
2 stage collar set at 1260' circ to surface with 300 sk cem. No pipe recovered.
Pumped down 5 1/2 csg with 25 sk cem. -30 sk gel & water W/400 lbs hulls -released
plug and pumped 50 sk cement. MPP 300 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED
DATE 5/8/74
INV. NO. 9038-W