

70
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1965
8-13-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frontier Oil Co 15051-301-01-00-00
Complete Address: 1720 Wichita Plaza, Wichita, Kans
Lease Name Madden Well No. 6
Location SE NW NE Sec. 4 Twp. 13 Rge. (E) (W) 17
County Ellis Total Depth 3622
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: same
Address: License No.
Operation Completed: Hour 8AM Day 12 Month 8 Year 65

The Above well was plugged as follows:

8 5/8" 200' circulated with cement.
Circulated hole with heavy mud, set plug at 540' with 1/4 sack
hulls and displaced 20 sax cement through drill pipe, heavy mud
to 180', set plug 1/4 sack hulls and displaced 20 sax cement
through drill pipe, heavy mud to 35', set plug, 1/4 sack hulls
and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Edmond Petty
Well Plugging Supervisor

8/13/65
1626-W