

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

DEC 27 1966  
12-27-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Tomlinson-Kathol Inc., 15:051-30404-00-00

Complete Address: 1125 Wichita Plaza Wichita, Kansas

Lease Name Wolf Well No. 1

Location C S/2 SE NE Sec. 4 Twp. 13 Rge. 17 (E) (W) X

County Ellis Total Depth 3620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: E-B Drilling Co. Inc.,

Address: Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 30 A Day 21 Month 12 Year 1966

The Above well was plugged as follows:

RTD 3620' 8 5/8 csg set at 188' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 20 sc cem.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cem. thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

12/27/66...  
4526-W