

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1963
3-15-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name M. J. Bove 15-051-02679-00-00
Complete Address: 754 Wichita Ave Russell, Kans
Lease Name Wolfe Well No. 2
Location NE SE SW Sec. 4 Twp. 13 Rge. (E) (W) 17
County Ellis Total Depth 3560
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Barnes & Sons & Sun Cementing Co
Address: Russell, Kansas License No. 9
Operation Completed: Hour 5PM Day 9 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 202' circulated with cement - 5 1/2" 3555' with 60 sax cement.

Halliburton Retainer plugs at 3290' - filled with sand to 3070'. Hole in 5 1/2" in Dakota section. pulled 709' 5 3/8" to 550', circulated hole with heavy gel mud through 5 1/2" at 550' (-16 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edwin Petty
Well Plugging Supervisor

DATE: 3/15/63
INV. NO. 6724-U