

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-115-00559-0000

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name E. H. Adair Oil Co.

Complete Address: 1005 E. Second Street, Wichita, Kansas.

Lease Name Deplor Well No. 4

Location S7 S4 SE Sec. 26 Twp. 21 Rge. 4 (E) X(M)

County Marion Total Depth 2458'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Company tools

Address: Same License No.     

Operation Completed: Hour 3:30PM Day 5 Month 8 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 2458' back to 2445', ran 5 sack cement w/ dump bailor.  
Ripped off and pulled 5 1/2" casing, filled hole w/ mud from 2410' back to 160' set a  
10' rock bridge and ran 20 sack cement from 150' back to 90'. Filled hole w/ mud from  
90' back to 30' set a 5' bridge and ran 8 sack cement from 25' back to zero 4' below  
ground level. 8 5/8" surface pipe 4' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Robert W. James  
Well Plugging Supervisor

DATE 8-8-63

INV. NO. 8030-F