

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 113-11

LOCATION NW NW SW

SEC. 27 TWP, 11 RGE. 17

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 15 Lease Baumer

Operator Deep Rock Oil Corp Address Hutchinson, Kans

Field Bemis County Ellis

Total Depth 3721 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 1300' circulated with cement - 7" at 3655' with
17 1/2 sax cement behind - Lane Wells plugs to 3250' - Top perforations
at 3220' -

Filled with chat and sand to 3209' - set 4 sax cement with dump bailer
pulled 2850' 7" casing - filled with mud to 250' - set rock
bridge and 20 sax cement - filled with mud to 35' - set rock
bridge and 10 sax cement to bottom cellar.

RECEIVED
 STATE CORPORATION COMMISSION

DEC - 3 1951

CONSERVATION DIVISION
 Wichita, Kansas



District Conservation Agent

Date 11-30-50

PLUGGING

FILE SEC 27 T 11 R 17
 BOOK PAGE 113 LINE 11