

15-051-19404-0000

Form CP-3
Rev. 6-26-62

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address: Box 553 Russell, Kansas 67665

Lease Name Giebler "A" Well No. 1

Location SW NW SE Sec. 27 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3910'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. Tools Haliburton Co.

Address: Hays, Kansas License No.

Operation Completed: Hour 6P Day 25 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 3910' 8 5/8 csg set at 213' cwc

5 1/2 csg set at 3910' cw 150 sk cmt.

5 1/2 csg squeezed at 800' W/200 sk comm cmt.

No. pipe recovered

Tubing set at 3556 Displaced 35 sk cmt. (3140-3556)

Tubing Pulled to 1500' circulated gel (20 sk) to surface. Set 15 sk cmt plug. (1320-1500)

" " " 720' set 15 sk cmt plug. (540-720)

" " " 210' circ. cmt (15 sk) to surface.

Cutoff 5 1/2 & 8 5/8 csg. Filled annulus with 50 sk cmt.
I hereby certify that the above well was plugged as herein stated.

Signed: *R. J. Massey*
Well Plugging Supervisor

INVOICED
3/27/69
9522-W