

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 15-051-05399-00-00
71-41

LOCATION NW NE SW

SEC. 27 TWP. 15 RGE. 20

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Karlin

Operator Imperial Drg Co Address 903 Union Natl Bldg Wichita,

Field _____ County Ellis

Total Depth 3882' Feet.

Plugging Contractor Earl Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 227' circulated with cement - 5 1/2" at 3848' with 150 sax
cement behind - perforated at 3838'.

Filled with chat to 3830', set 4 sax cement with dump bailer, pulled
2050' 5 1/2" - filled with heavy mud to 225', set rock and 10 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

DIGGING
FILE NO. 27-13-R-2011
BOOK PAGE 21 LINE 41

10-29-54

Edson J. ...
District Conservation Agent
Date 10-25-54