

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply, Inc. 15-051-01343-00-00

Complete Address: Box 169 Russell, Kansas 67665

Lease Name Waldschmidt "A" Well No. 2

Location NE NW NW Sec. 27 Twp. 13 Rge. 20 (E) (W) XX

County Ellis Total Depth 3890'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 4:30P Day 15 Month 1 Year 1969

The Above well was plugged as follows:

Total Depth 3890' 8 5/8 csg set at 227' cwc

5 1/2 csg set at 3890' cw 150 sc cmt.

5 1/2 stage collar set on Anhydrite(1650) CWC 500 sc.

5 1/2 csg filled with sand(3875-3890) Dumped 5 sc cmt W/dump bailer.(3835-3875)

5 1/2 csg filled with mud to 700'. 10' BK and 5 sk cmt.

Cutoff and recov. 477' of 5 1/2 csg.

Set Rk Brdg. (215-225) Cement plug 20 sks.(175-215)

Mud to 40' Set 5' BK and 10 sk cmt to surface.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: Russ F. Massey
Well Plugging Supervisor

INVOICED

DATE

1/17/69

INV. NO.

9199-W