

Y

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Spector Pipe & Supply, Inc. 15-051-02892-00-00

Complete Address: Box 169 Russell, Kansas 67665

Lease Name Waldschmidt "A" Well No. 3

Location SW NE NW Sec. 27 Twp. 13 Rge. 20 (E) (W) XX

County Ellis Total Depth 3830'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 4P Day 18 Month 1 Year 1969

The Above well was plugged as follows:

Total Depth 3830' 8 5/8 csg set at 230' cwc.

5 1/2 csg set at 3827' cw 150 sc cmt.

5 1/2 stage collar set on anhydrite(1645) and cwc 500 sc.

5 1/2 csg filled with sand (3800-3830) dumped 5 sc cmt W/dump bailer. (3760-3800)

Set 5 1/2 plug and 5 sk cmt. plug at 700'.

Mud to 225' set rock bridge and 25 sk cmt. plug.

Mud to 40' set rock bridge and 10 sk cmt. to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo. J. Manning*
Well Plugging Supervisor

INVOICED
DATE 1/20/69
INV NO. 9205-U