

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply, Inc. 15-051-02895-00-00

Complete Address: Box 169 Russell, Kansas 67665

Lease Name Waldschmidt "A" Well No. 6

Location SE NW NW Sec. 27 Twp. 13 Rge. 20 (E) (W) XX

County Ellis Total Depth 3829'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 4P Day 17 Month 1 Year 1969

The Above well was plugged as follows:

Total Depth 3829' 8 5/8 csg set at 175' cwc.

5 1/2 csg set at 3829' cw 150 sc cmt.

5 1/2 stage collar set on Anhydrite (2650) cwc 500 sc.

5 1/2 csg filled with sand (3800-3829) dumped 5 sc cmt W/dump bailer. (3760-3800)

Mud to 700'. Set plug, 10' sand and 5 sk cmt. plug.

Mud to 170' set 5' rk bridge and 25 sk cmt. plug.

Mud to 40' set 5' rk and 10 sk cmt. to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE: 1/20/69
INV. NO. 9206-W