

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 7 1965

15051-30214-00-00

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name V. Francis Weigal

Complete Address: Gorham, Kansas

Lease Name Giebler Well No. 1

Location CSE SW Sec. 27 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3863

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Deiling & Sone Drg Co

Address: Victoria, Kans License No.     

Operation Completed: Hour 8AM Day 6 Month 10 Year 65

The Above well was plugged as follows:

8 5/8" 202' circulated with cement.

Circulated hole with heavy mud, set plug at 540', displaced 20 sax cement  
 through drill pipe, heavy mud to 180', set plug and displaced 20 sax  
 cement through drill pipe, heavy mud to 35', set plug, hulls and filled  
 to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leon Petty  
Well Plugging Supervisor

10/7/65  
1944-11