

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Dresh
Administrator
500 Insurance Building
Wichita, Kansas 67203

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Harold Ebert 15-051-20493-00-00

Complete Address 1011 Meadowbrook Rd. Iola, Kansas

Lease Name Giebler "A" Well No. 1

Location SE NE SW Sec. 27 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3854'

Abandoned Oil Well Gas Well Input Well SWD Well D & AXI

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 10:30A Day 6 Month 9 Year 1969

The above well was plugged as follows:

RTD 3854' 8 5/8 csg set at 250' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Mason
Well Plugging Supervisor

DATE 9/8/69
INV. NO. 426-4