

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051 - 22,893-00-00 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Grant Oil-Remco L. T. D. 1981

Complete Address 1950 S. Jewell Ave., Suite 106, Denver, Co. 80226

Lease Name Brungardt Well No. 1-30

Location SE SE SE Sec. 30 Twp. 14 Rge. 16 (East) (West)

County Ellis Total Depth 3560'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldrill Exploration

Address P.O. Box 11245, Wichita, Ks. 67211 License No. \_\_\_\_\_

Operation Completed: Hour: 8:45PM Day: 12 Month: March Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-180' S.P. cuc. w/200 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridg of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 180' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
03-15-1982  
MAR 15 1982

Signed: \_\_\_\_\_  
Conservation Division Agent  
Wichita, Kansas

3-16-82  
INV. NO. 9653-W