

15-051-05156-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CN $\frac{1}{2}$  N $\frac{1}{2}$  NE

SEC. 28 TWP. 14 RGE. 16

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 8 Lease Dinkel

Operator Courtney G. B. Davis Address RFD 5 Newton, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3375 Feet.

Plugging Contractor R & D Pipe Pulling Co

Plugging Contractor's License No. 236

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 965' circulated with cement. 5 1/2" 3359' with 75 sax  
cement behind.

Filled with sand to 3350', set 5 sax cement with dump bailer, pulled  
2900' 5 1/2" - filled hole with heavy chunk mud to 450', set rock and  
20 sax cement, heavy chunk mud to 200', set rock and 15 sax cement,  
heavy chunk mud to 40', set 10' rock bridge and 10 sax cement to  
bottom cellar.

*E. L. [Signature]*  
District Conservation Agent

Date 12.15.57

PLUGGING  
FILE SEC 28 T 14 R 16 W  
BOOK PAGE 68 LINE 11

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1957  
12-17-1957  
CONSERVATION DIVISION  
Wichita, Kansas