

15-051-05154-00-00
B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NE

SEC. 28 TWP. 14 RGE. 16

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Dinkle 402 Union Natl. Bldg.

Operator C. B. Davis Address Wichita, K.

Field _____ County Ellis

Total Depth 3390 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 213' circulated with cement - 5 1/2" at 3362 with

75 sax cement behind and squeezed with 200 sax cement.

Filled with sand to 3350' set 4 sax cement with dump bailer,

pulled 2750' 5 1/8" - pumped hole full mud (30 sax) pumped

cementing plug to 250' followed by 80 sax cement - cement

250' to 0' (100# standing pressure)

Mudding and cementing by Halliburton Co)

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1955
07-12-1955
CONSERVATION DIVISION
WICHITA, KANSAS

John Lee
District Conservation Agent

Date 7-8-55

PLUGGING
FILE SEC 28 T 14 R 16W
BOOK PAGE 133 LINE 16