

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-21, 873-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name R.P. Nixon Operations

Complete Address 207 W. 12st, Hays, Ks. 67601

Lease Name Schippers Well No. 2

Location W/2 NW SW Sec. 36 Twp. 14 Rge. 16 (East) West

County Ellis Total Depth 3433'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No.

Operation Completed: Hour: 12:45 PM Day: 6 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8"-S.P. 210' euc. w/common cement. 4 1/2" set at 3432' w/ 125 sacks common cement. Pushed plug to plug off bottom to 2800' w/50' of sans & 4 sacks cement. Shot pipe 6 times & recoverd 1762'. Ordered 165 sacks 50/50 posmix-4% Gel.-3% Cal. C1. Pumped into 8 5/8" S.P. w/pump truck, 4 sacks hulls, 25 sacks cement, 15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sacks hulls, released plug & followed w/70 sacks cement.

Maximum pressure 700 pounds.

Amount of Surface Casing: 210' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

7-13-82
620-W

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1982
07-12-1982
CONSERVATION DIVISION
Wichita, Kansas