

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

*Rec'd  
15-051-1984*

API Number 15-051 - 22,839-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name R.P. Nixon Oil Operation

Complete Address 207 W. 12th, Hays, Ks. 67601

Lease Name Schippers Well No. A-3

Location C of S/2 SW NW Sec. 36 Twp. 14 Rge. 16 (East) West

County Ellis Total Depth 3421'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Jay-Lan Corporation

Address 207 W. 12th, Hays Ks. 67601 License No. \_\_\_\_\_

Operation Completed: Hour: 4:30 PM Day: 10 Month: Feb. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-222' S.P. cuc. W/ 140 sacks common 2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel.-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' W/ 70 sacks cement

2nd plug @ 210' W/ 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 222' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: *[Signature]*  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

*2-17-82  
8442-W*