

15-051-00857-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1962
09-27-1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co.
Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas
Lease Name Wagner Well No. 1
Location NW NW SW Sec. 36 Twp. 14 Rge. (E) (W) 16
County Ellis Total Depth 3430
Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 6PM Day 25 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 238' circulated with cement - 5 1/2" 3430' with 125 sax cement - perforations 3412'.

Sand back to 3400', set 4 sax cement with dump bailer - pulled 2876', 5 1/8" to 500', circulated hole with heavy mud through 5 1/2" at 500' (33 sax gel) - displaced 20 sax cement through 5 1/2" at 440', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', filled with cement 35' to bottom cellat.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/21/62
INV. NO. 5996-u

Signed: [Signature]
Well Plugging Supervisor