

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32278
Name: Tengasco, Inc.
Address 1: PO Box 458
Address 2: 1327 Noose Rd.
City: Hays State: KS Zip: 67601 +
Contact Person: Gary Wagner
Phone: (785) 625-6374
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E-23,738 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3303 Bottom: 3434 T.D. 3783
Arbuckle Depth to Top: 3703 Bottom: 3720 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 165-21,136-00-01
Spot Description: _____
NE NW NW Sec. 30 Twp. 16 S. R. 16 East West
330 4946 Feet from North / South Line of Section
1120 4144 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rush
Lease Name: Urban D Well #: 4
Date Well Completed: 10-83
The plugging proposal was approved on: 10-29-10 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 11-3-10
Plugging Completed: 11-3-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	1100'	
		Production	4-1/2"	3783'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 2 holes @ 1130'. Ran tbg @ 3445, pumped 10 sx gel & 50 sx cmt w/ 200# hulls, tbg @ 1200', pumped 235 sx cmt to circulate cmt up 8-5/8". Pulled tbg & topped off csg w/ 5 sx 60/40 4% gel.

RECEIVED

NOV 12 2010

KCC WICHITA

Plugging Contractor License #: 32332 Name: Fischer Well Service
Address 1: PO Box 733 Address 2: _____
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-3837
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Gary Wagner

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202