

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6407
Name: Flowers Production Co., Inc.
Address 1: P.O. Box 249
Address 2: _____
City: El Dorado State: KS Zip: 67042 + _____
Contact Person: Dallas Flowers
Phone: (316) 321-0550
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Bartlesville Depth to Top: 2798 Bottom: 2864 T.D. 2910
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 015-23681-0000
Spot Description: _____
E2 W2 NE Sec. 29 Twp. 29 S. R. 5 East West
1,328 4650 Feet from North / South Line of Section
1,058 1691 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Butler
Lease Name: Flowers Pottorff Well #: 1-29
Date Well Completed: 3-2006
The plugging proposal was approved on: 11-4-10 (Date)
by: Duane Krueger (KCC District Agent's Name)
Plugging Commenced: 11-4-10
Plugging Completed: 11-4-10

GPS REC

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Bartlesville 2798-2864</u>	<u>water</u>	<u>surface</u>	<u>8 5/8"</u>	<u>210</u>	<u>none</u>
		<u>production</u>	<u>4 1/2"</u>	<u>2909'</u>	<u>none</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH W/Tbg @ 2794', Consolidated mixed & pumped 25 SXS 60/40 Pozmix 4% Gel 3% CC & Displaced in Casing. Tagged cement @ 2810'. RIH W/Rubber Plug & Tbg @ 2700', Consolidated mixed & pumped 20 SXS 60/40 Pozmix 4% Gel, 3% CC, & displaced in casing. Tagged Cement @ 2271'. Pressured casing, held ok. Shot cement squeeze holes @ 260'-261'. Swedged into 4 1/2" casing, established circulation, & Consolidated mixed & pumped 90 SXS 60/40 Pozmix 4% Gel to surface. Cement circulated plug down 11-4-2010, 5:00 PM. Consolidated cement ticket # 29224.

DP

Plugging Contractor License #: 32701 Name: C&G Drilling, Inc.
Address 1: 701 East River St. Address 2: _____
City: Eureka State: KS Zip: 67045 + _____
Phone: (620) 583-4306
Name of Party Responsible for Plugging Fees: Dallas Flowers
State of Kansas County, Butler, ss.
Dallas Flowers Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

RECEIVED

NOV 16 2010

KCC WICHITA