

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31174
Name: Bighorn Oil Company, Inc.
Address 1: P.O. Box 263
Address 2: Great Bend 67530
City: Herington State: KS Zip: 67544 + 0263
Contact Person: Brad Swalley
Phone: (620) 793-3160
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-20736-0001
Spot Description: SE/4
SW NE SE Sec. 1 Twp. 18 S. R. 14 East West
1,650 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Demel Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 10/5/10 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 10/21/10
Plugging Completed: 10/22/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	792'	
		Production	5 1/2"	3325'	TOC @ 2580

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 50 sacks cement & 200# hulls down 5 1/2" casing; max. pressure 750#. Tagged cement at 2850'. Ripped casing at 1810', 1730' & 1520'; pipe came free at 1520'. Pulled to 1500' & pumped 125 sacks cement & 300# hulls. Pulled to 800' & pumped 50 sacks cement. Pulled to 450' & pumped 50 sacks cement. Pulled to 200' & circulated 65 sacks cement to surface. Pulled rest of casing.

RECEIVED

NOV 17 2010

KCC WICHITA

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3410
Name of Party Responsible for Plugging Fees: Bighorn Oil Company, Inc.
State of Kansas County, Barton , ss. Rickey Papp **Agent**
Rickey Papp Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rickey Papp