

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201 **GPS KCC**  
City: Hays State: KS Zip: 67601 +  
Contact Person: Mark Leiker  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
KC Depth to Top: 3814 Bottom: 3978 T.D. 4045  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 065-30222-0000  
Spot Description: \_\_\_\_\_  
150' W SE SW Sec. 29 Twp. 8 S. R. 25  East  West  
4620 660 Feet from  North  South Line of Section  
1980 3450 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Graham  
Lease Name: Knoll North Unit Well #: S #2  
Date Well Completed: 12-24-1966  
The plugging proposal was approved on: 11-9-10 (Date)  
by: Darrell Dipman (KCC District Agent's Name)  
Plugging Commenced: 11-9-10  
Plugging Completed: 11-9-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LKC		Surface	8 5/8	218	None
		Production	4 1/2	4043	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Move in Professional Pulling Services rig #5, Rig up, put on workover head, run catcher, tag sand 3355', wash down to plug @3375', cir. clean, release and pull plug. Rig up Perf Tech, perf 2230', 1450', 185', run tubing open end, tag fish @3415', nux 175 sx cement and 500# hulls. Pull tubing to 1308' mix 20 sx cement, cir to surface. Close valve on 4 1/2, mix 50 sx down anulus, shut in. Pull tubing, fill 4 1/2 with 15 sx, used total 260 sx 60/40 pos 4% gel, and 500# hulls. Rig down, move off.

Plugging Contractor License #: 32810 Name: Professional Pulling Services  
Address 1: P.O. Box 486 Address 2: \_\_\_\_\_  
City: Hays State: KS Zip: 67601 +  
Phone: ( 785 ) 628-7443  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick ss.  
Mark Leiker  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Leiker

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOV 17 2010

KCC WICHITA