

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: 2020 N Bramblewood, Wichita KS 67201
City: Hays State: KS Zip: 67601 +
Contact Person: Robert Grant
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARB Depth to Top: 3224' Bottom: 3244 T.D. _____
ARB Depth to Top: 3262 Bottom: 3265 T.D. _____
ARB Depth to Top: 3270 Bottom: 3274 T.D. _____
ARB 3278 3303
ARB 3353 3360

API No. 15 - 159-02683-0000
Spot Description: _____
NE - SE - SW Sec. 25 Twp. 20 S. R. 9 East West
990 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Tobias Well #: 17
Date Well Completed: 5-23-63
The plugging proposal was approved on: 10-25-10 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 11-3-10
Plugging Completed: 11-4-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
AR Buckle	Oil/Water	Surface	8 5/8	203'	0
		Long String	5 1/2	3353'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

11-3-10 Perf 2 holes @ 700' and 253'. Ran tubing to 1064' got out side of pipe. 1064 - 50 sx common 150# hulls pull to 700' 35 sx common, pull to 255' 165 sx common cement didn't circ to surf.

11-4-10 Run tubing tag @ 812' 50 sx common 200# hulls pull to 255' 35 sx common. Circ cement to surface. Pull tubing hook to 5 1/2, 10 sx common press to 500#. Hook to 8 5/8, 165 sx common, quit pumping on vacuum. Witnessed by Virgil Clothier, KCC Wichita. DR

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: 2020 N. Bramblewood, Wichita, KS 67206
City: Hays State: KS Zip: 67601 +
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Robert Grant
State of Kansas County, Sedgwick, ss.
Robert Grant Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Robert Grant

RECEIVED
NOV 22 2010

KCC WICHITA