

15-051-21873-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED Form CP-4  
STATE CORPORATION COMMISSION Rev. 12-15-80  
07-12-1982  
JUL 12 1982  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ellis SEC. 36 TWP. 14S RGE. 16W E/W  
Location as in quarters or footage from lines:  
W/2 NW SW


Lease Owner R.P. Nixon Operations  
Lease Name Schippers #2 Well No. \_\_\_\_\_  
Office Address 207 W. 12th Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 6-28-82  
Plugging completed 7-6-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3433'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	210'	none
				4-1/2"	3432'	1778'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Ran 50' of sand and 4 sacks of cement and pushed bottom plug to 2800'. Shot casing  
@2679', 2361', 2191', 2029', 1914' and 1782'. Pulled a total of 47 joints of 4-1/2"  
casing. Plugged well with 4 sacks hulls, 25 sacks cement, 15 sacks gel, 70 sacks  
cement, 4 sacks gel, 1 sack hulls, released plug and displaced with 70 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Kansas 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of July, 19 82

My Commission expires: 

Irene Hoover  
Notary Public.